

ASSAM CANCER CARE FOUNDATION (ACCF)
3rd floor, V.K. Trade Centre, G.S. Road, Opp. Down-town Hospital,
Guwahati – 781022, Assam Ph: +91-90852 02020
E: procurement@accf.in | W: www.assamcancercarefoundation.org

FOR SELECTION OF CONTRACTOR FOR INTERIOR FIT-OUT WORKS OF CANCER CARE CENTER HOSPITAL BLOCK IN ASSAM
FOR ASSAM CANCER CARE FOUNDATION

Ref: ACCF/Interior/2021-22/21 dated 28.06.2021

CORRIGENDUM No. 1

Date: 09.07.2021

Amended BoQ is also uploaded for price bid. Bidders need to fill the price in the amended BoQ only.

Bid submission date extension:

Sr.No.	Tender Clause No	Existing Term	Amendment
<u>1</u>	Important Dates of e-Tender	- Online Technical & Financial Bid Submission Date 13-July-21 14:30 Hrs. - Hard copy submission (all document) Date: 13-July-21 14:30 Hrs. - Bid Opening Date – Technical (online) Date:13-July-21 15:00 Hrs.	- Online Technical & Financial Bid Submission Date 16-July-21 14:30 Hrs. - Hard copy submission (all document) Date: 16-July-21 14:30 Hrs. - Bid Opening Date – Technical (online) Date:16-July-21 15:00 Hrs.

Other Amendment /Clarification are mentioned below (since BoQ has also been revised, the revised BoQ shall prevail in case of any further query or conflict. Bidders be informed accordingly):

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
1.	2.1.9	Time Line of Completion Category L1-80 days,L2-60 days,L3-45 days	L1-180 days, L2-160 days, L3-140 days	Time Line of Completion including mobilization time. L1 - 120 days L2 - 90 days L3 - 60 days
2.	3.9	SETTLEMENT OF DISPUTES, ARBITRATION:-(a) In case of Dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with the Contract, such disputes or difference shall be settled in accordance with the Arbitration and Conciliation Act, 1996. The parties shall make efforts to agree on a sole arbitrator and only if such an attempt does not succeed and the Arbitral Tribunal consisting 3 arbitrator one each appointed by the Employer and the Contractor and the third arbitrator to be chosen by the two Arbitrators so appointed by the parties to act as Presiding Arbitrator shall be considered. In case of failure of the two arbitrators appointed by the parties to reach upon a consensus within a period of 30 days from the appointment of the arbitrator appointed subsequently, the Presiding Arbitrator shall be appointed jointly by the Employer and the Contractor.	A Dispute shall be referred to the Governance Body for resolution through mutual discussions. If the Dispute is not resolved within a period of 7 (Seven) days from the date of reference thereof to such committee, then the Dispute shall be referred to a committee of directors consisting of one authorized director of each party for amicable resolution. In the event that the Dispute cannot be amicably resolved within a further period of 30 (thirty) days from the date of reference to the committee of directors, then the following provisions shall apply. If a Dispute is not resolved, the Dispute shall be resolved by arbitration in accordance with the provisions of the Arbitration and Conciliation Act, 1996. The place of such arbitration shall be Guwahati, Assam, and the language of arbitration proceedings shall be English.	SETTLEMENT OF DISPUTES, ARBITRATION:-(a) In case of Dispute or difference arising between the Employer and the Contractor relating to any matter arising out of or connected with the Contract, such Dispute shall be referred to the Governance Body for resolution through mutual discussions. If the Dispute is not resolved within a period of 15 days from the date of reference thereof to such committee, then the Dispute shall be referred to a committee of directors consisting of one authorized director of each party for amicable resolution. In the event that the Dispute cannot be amicably resolved within a further period of 30 (thirty) days from the date of reference to the committee of directors, then the following provisions shall apply. Such disputes or difference shall be settled in accordance with the Arbitration and Conciliation Act, 1996. The parties shall make efforts to agree on a sole arbitrator and only if such an attempt does not succeed and the Arbitral Tribunal consisting 3 arbitrator one each appointed

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
				by the Employer and the Contractor and the third arbitrator to be chosen by the two Arbitrators so appointed by the parties to act as Presiding Arbitrator shall be considered. In case of failure of the two arbitrators appointed by the parties to reach upon a consensus within a period of 30 days from the appointment of the arbitrator appointed subsequently, the Presiding Arbitrator shall be appointed jointly by the Employer and the Contractor.
3.	3.25 a.	Payments shall be made as per the payment mechanism proposed by the Engineer and agreed by the Bidder and Client as part of the award of Contract.	Payments shall be made on Prorata basis as per Rate and quantity of individual items actually executed. Minimum Frequency of bill shall be 15 Days.	fortnight Running bill shall be made after due approval from PMC & site engineer
4.	4.1.16	ACCF will provide one-point source for Electricity and Water on chargeable basis @1% of contract price. Distribution from the source point to location of works will be in contractor's scope.	Water and Electricity - Free of cost or chargeable, please clarify	Space, Water, electricity shall be provided by ACCF without any cost to vendor.
5.	4.1.21	URGENCY OF WORK-The work being of very urgent nature shall be carried out with all efforts by the Contractor to complete it in all respects within the stipulated time of completion. The progress of the work as shown in work program shall be continued, by the Contractor even if any dispute arises between the Contractor and ACCF on any matter connected with the work and contractor	comments/query raised by LnT for dispute settlement.	URGENCY OF WORK-The work being of very urgent nature shall be carried out with all efforts by the Contractor to complete it in all respects within the stipulated time of completion. The progress of the work as shown in work program shall be continued, by the Contractor even if any dispute arises between the Contractor and ACCF on any matter connected with the work and contractor approaches aritrator/legal authority for settlement of the dispute as per dispute

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		approaches legal authority for settlement of the dispute, on being not satisfied with the decision of ACCF on the matter of dispute. The continuation of progress of the work should not be hampered in any case by both parties and order given by legal authority on matter of dispute shall be binding on the parties.		settlement clause, on being not satisfied with the decision of ACCF on the matter of dispute. The continuation of progress of the work should not be hampered in any case by both parties and order given by legal authority on matter of dispute shall be binding on the parties.
6.	4.1.5.10	Idling charges -No idling charges will be paid.	Request to delete.(Not in line with our original Contract)	No idling charges shall be paid
7.	4.1.5.5 (a)	a)For delay in Completion: In case the Completion Date is beyond the Intended Completion Date for each site location, liquidated damages (L.D) will be levied at the rate of one per cent 1% of the Work Order Value for such site location per week of delay (or part thereof), subject to a maximum of 5 per cent of the Work Order Value for such site location	For delay in Completion:, the Contractor shall pay to the Employer damages for delay calculated at the rate of 1 % (one per cent) of the Contract Price attributable to the unfinished value of work, for the respective Site per month of delay (or part thereof), subject to a maximum of five per cent (5%) of the Contract Price, between the relevant Time for Completion and the date stated in the Completion Certificate.	a)For delay in Completion: In case the Completion Date is beyond the Intended Completion Date for each site location, liquidated damages (L.D) will be levied at the rate of one per cent 1% of the unexecuted Work Order Value for such site location per week of delay (or part thereof), subject to a maximum of 5 per cent of the Work Order Value for such site location. After that ACCF may terminate the contract and issue work order to other party at the risk and cost of the selected vendor.
8.	4.1.5.5 (b)	b)If there are any major mistakes found in taking measurements, Client will impose a penalty by deducting 1% of Work Order Value of the contractor per mistake. Mistake shall be considered as major if the deviation observed in measurement is more than 10%.	Request to delete.(No definition of mistake available. Unlimited liability - no upper limit of penalty.)	b)If there are any major mistakes found in taking measurements, Client will impose a penalty by deducting 1% of Work Order Value of the contractor per mistake up to maximum 10% penalty then after which ACCF may terminate the contract. Mistake shall be considered as major if the deviation

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
				observed in measurement is more than 10%.
9.	4.1.5.5 (c)	c)Mistake in Conducting quality control: Client may impose a penalty of 2% of the Work Order Value of the Contractor for each mistake. For five such mistakes occurring the Quality Control Engineer shall be removed from his/her position immediately.	Request to delete.(No definition of mistake available. Unlimited liability - no upper limit of penalty.)	Contractor has to abide by all the specification, concept, design intent, make and approved drawings. Vendor should execute work as per design intent. If not found at any moment of time during ongoing work, penalty at 0.5% of contract value shall be imposed in addition of redo the work without any extra. penalty under this will be up to maximum 5% of the contract value, beyond this ACCF may terminate the contract with forfeiture of security amount and assign contract to another bidder at the risk and cost of selected bidder.
10.	4.1.5.5 (d)	If the Contractor doesn't implement the organization structure as per the Bid, the contractor shall be liable for penalty of 2% of the fee	Request to delete.(Not in line with our original Contract)	Contractor shall depute full time site supervisor for each site along with adequate supporting staff for executing work. Supervisor shall be at least graduate. If supervisor is not available at site during working hours then 0.5% of contract value shall be imposed. For repeated offence penalty shall be 1% per incidence up to maximum 5% of the contract value. beyond this ACCF may terminate the contract with forfeiture of security amount and assign contract to another bidder at the risk and cost of selected bidder.
11.	4.1.5.9	Extra Items-Cost of Material + Wastage+ Labour +10% +GST	Any other Items not included in the scope of work will be incorporated in the WO and paid based on amount arrived	No change as this is common Market criteria

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
			at based on Cost of Material, Labour, Plants and Machinery, outsourced specialized services, if any Plus 12.5% towards Contractor's OHP. GST will be Extra.	
12.	BoQ	Rolling Stools for OT	It will be in clients scope, please confirm	Rate need to be quoted as per BoQ
13.	BoQ	Rolling Stools for Consultation Room	It will be in clients scope, please confirm	Rate need to be quoted as per BoQ
14.	BoQ	10S Island Seat (Reception) -Fabricating and Supply of Floor Mounted 10S Island seat with BWR Ply and M/S framework as required with BWR Ply cover / Flexiply cover with PU Leather finish as per approved colour, all complete as per architect's drawing.	Please share size	For basic size please refer drawing. Detailed drawing shall be prepared by Vendor.
15.	BoQ	Center Table - 450x900MM:Table of size 900mm(W)x500-600(D) x400mm(H) - with Acrylic Solid surface (Corian - Camio White shade or approved shade) center table of thickness 50mm and necessary 12mm Plywood backing, fixed onto SS 304 Brush finished 30mm square tube framing of 1.5mm thk. Shall include all necessary bush, hardware, glue infill of matching colour as per Acrylic solid surface manufacturer.	Image and description differs, please specify what to follow	Image shown in Concept presentation has to be followed here. Specification to the item no. 2.01 is changed as "Center table of size 900mm(W)x 450mm(D) x400mm(H) with Table top box-up of thickness 50mm made of necessary 12mm Plywood backing finished with 1mm Laminate of approved make and shade. Bottom of table top shall be finished with Laminate of approved shade. Table top shall be fixed onto SS 304 Brush finished 25mm square tube framing of 1.5mm thick. as per detailed drawing. Shall include all necessary bush, hardware etc. all complete for the supply of finished product. Approved Laminate – GREEN LAM LAMINATES - 5018 Brooks "

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
16.	BoQ	Bamboo Seater- Type 1 (Reception) -Fabricating and Supply of Floor Mounted Bamboo Seat with Necessary Ply and MS Framework all complete as per detail drawing.	Please share size	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.
17.	BoQ	Bamboo Seater- Type 2 (Reception / OPD Lounge) -Fabricating and Supply of Floor Mounted Bamboo Seat with Necessary Ply and MS Framework all complete as per detail drawing.	Please share size	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.
18.	BoQ	Glazed Doors fixed with Full Glazed partitions on Patch fittings	Please share door size and hardware schedule	Door size: 2200 x 1050 mm approx, patch fitting will not be required. Minimum 12 mm thick toughened glass. Rate shall include providing all necessary hardware like heavy duty stainless steel floor springs, stainless steel pivot supports at top, SS D handle 300mm long, locking arrangement, including cutting notches / drilling holes in glass of required sizes etc all complete as per approved shop drawings. This hardware shall be of approved makes only.
19.	BoQ	Glazed Doors fixed with Full Glazed partitions on Patch fittings	1) Specification says Glazed door with Partition, Please clarify Item is only for Glazed door or with Partition. 2) Also need detailed specification of Door with glass thickness , Size and Hardware Schedule.	Door size: 2200 x 1050 mm approx, patch fitting will not be required. Minimum 12 mm thick toughened glass. Rate shall include providing all necessary hardware like heavy duty stainless steel floor springs, stainless steel pivot supports at top, SS D handle 300mm long, locking arrangement, including cutting notches / drilling holes in glass of required sizes etc all complete as

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
				per approved shop drawings. This hardware shall be of approved makes only.
20.	BoQ	Wall mounted Table (around Column) (Visitor) -Fabricating and Supply of Wall Mounted Ply Table in 1mm Laminate Finish and 2mm Edge Banding with Necessary Ply and MS Framework all complete as per detail drawing.	Please share size	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.
21.	BoQ	Cafeteria Wall Fixed Table (Visitor) -Fabricating and fixing of wall mounted High Table of depth 450mm all around the column / along specified length on wall etc with Ply supports in Laminate finish, including of all necessary hardware, 2mm edge banding all complete as per drawing.	Please share size	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.
22.	BOQ	Cafeteria Wall Fixed Table (Staff) -Fabricating and fixing of wall mounted High Table of depth 450mm all around the column / along specified length on wall etc with Ply supports in Laminate finish, including of all necessary hardware, 2mm edge banding all complete as per drawing.	Please share size	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.
23.	BOQ	Cafeteria Booth Seat (Staff) -Fabricating and supply of Booth seat 1000mm length - frames to be made of wooden batten and BWR ply. Seat and back rest to be made in ply, foam and leatherette(colour as per architect's selection).100mm thick foam (should be HR&FR rated) having ILD 41. , all complete as per architect's drawing .	Please share size	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
24.	BOQ	Column Seater (12S) (OPD Lounge) -Fabricating and supply of column-mounted circular seat around columns - frames to be made of wooden batten and BWR Ply. Saet and Backrest to be made with Ply / Flexi-Ply, with Solid Acrylic finish, all complete as per drawing.	Please share size	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.
25.	BoQ	Plywood paneling with Paint finish:Fabricating and fixing of 12mm BWR ply onto framework using 2.5mm thk aluminium box section of size 50mm x 75mm/ 60mm X 65mm on the existing wall surface by means of approved screws/nails and to be finished with 2 coat of Acrylic emulsion paint of approved shade over 2 coats of putty neatly finished to get a level surface. Shall be in proper line and level as per architects instructions, all complete.	Its better if we do MDF with paint finish instead of ply, please confirm if we can quote for MDF instead of ply	As per BoQ and specification only.
26.	BoQ	Lacquered glass panelling (Reception / Nurse's Station):Providing & Fixing 8mm thk Lacquered Glass (Saint Gobain) on over the plywood backing. Cost to include Adhesive: Clear Neutral Silicon of make GE winsil 20 / silpruf or DOW CORNING 789/995; Procedure: Apply all along the periphery & Horizontal lines @ 50mm c/c across the full surface on the backing ply, of required strength to hold the glass safely. Glass shall be precisely cut to size & edges to be machine polished. Cost to include 12mm Plywood backing with	Please confirm if framing is required or not	Framing is required. Framing size: 50 x 50 x 2.5(thickness) mm to be used as per detailed drawing to be prepared by vendor and as per approval of client/consultant.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		antitermite treatment and Bottomline; coner guard as per drawing with 3M double side tape and hat chanel of 5 - 10mm as per drawing. Rate to be inclusive of wastage. color as per architects design.Make : Saint gobain , Model : Ultra white or any other approved shade		
27.	BoQ	Column Paneling with Laminate (Reception):Providing and Fixing 6mm flexi-ply frame work on column with aluminum framework up to 3150mm and finished it with approved laminate to be fixed.	Please confirm if only single skin of ply will be sufficient	Single skin Flexi ply 6mm thick shall be provided. The Vendor shall provide necessary aluminum framings (50 x 50 x 2.5 mm) to achieve a smooth profile as per detailed design drawings.
28.	BoQ	Column Paneling with Mirror (Reception):Providing and Fixing BWR ply on aluminum frame work using 50x75mm 2.5mm gauge aluminum box section on Wall up to 3150mm and finished it with approved 6mm Mirror from floor upto bottom of the ceiling, sizing all as per drawing, with necessary hardware, adhesives, all complete	Please clarify mode of measurement, will it be perimeter x height, please confirm	Measurement will be in sq mt.
29.	BoQ	WALL VINYL GRAPHIC - TYPE -1: (Bamboo Strip Pattern 300 - 450mm wide) (Emergency /Chemo / General ward):Wall Vinyl of pattern uniformly as per manufacturers specifications, on wall surface / gypboard partitions / Gyp paneling. cost includes surface preparation, primer coats, levelling patti Colours as per architect's detail. Cost to include preparation on the punned	Please share basic rate	This is clarified as Acrylic Emulsion Stencil Painting not vinyl. Design - pattern already provided as per Concept presentation. Vendor shall quote as per rates arrived accordingly. Vendor Contact details as Below: M/s Emagine India- 9916631250 or M/s Blue Pebble- 9768199800 or M/s SIGNTIST Graphics - Mr. Praveen, 9884948600

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		surface for receiving the wall paper as per the manufacturer specification. NOTE : Interior Contractor must develop all the necessary Vinyl Graphics in required resolution using the Graphics Vendor. The Graphics should be matching in line with the Concept Presentation using Presets from the Vendor / Custom developed subject to Approval by Client / Architect.		NOTE : Interior Contractor must develop all the necessary Vinyl Graphics in required resolution using the Graphics Vendor. The Graphics should be matching in line with the Concept Presentation using Presets from the Vendor / Custom developed subject to Approval by Client / Architect.
30.	BoQ	WALL VINYL GRAPHIC - TYPE -1: (Bamboo Strip Pattern 300 - 450mm wide) (Emergency /Chemo / General ward):Wall Vinyl of pattern uniformly as per manufacturers specifications, on wall surface / gypboard partitions / Gyp paneling. cost includes surface preparation, primer coats, levelling patti Colours as per architect's detail. Cost to include preparation on the punned surface for receiving the wall paper as per the manufacturer specification. NOTE : Interior Contractor must develop all the necessary Vinyl Graphics in required resolution using the Graphics Vendor. The Graphics should be matching in line with the Concept Presentation using Presets from the Vendor / Custom developed subject to Approval by Client / Architect.	1) Please clarify, Items is wall graphics Film or Wall Graphic Paint.2) Also need basic Rate of Wall Graphics.	This is clarified as Acrylic Emulsion Stencil Painting not vinyl. Design - pattern already provided as per Concept presentation. Vendor shall quote as per rates arrived accordingly. Vendor Contact details as Below: M/s Emagine India- 9916631250 or M/s Blue Pebble- 9768199800 or M/s SIGNTIST Graphics - Mr. Praveen, 9884948600 NOTE : Interior Contractor must develop all the necessary Vinyl Graphics in required resolution using the Graphics Vendor. The Graphics should be matching in line with the Concept Presentation using Presets from the Vendor / Custom developed subject to Approval by Client / Architect.
31.	BoQ	ACRYLIC EMULSION PAINTING: (Stencil Type - 1 - Bamboo Pattern) (Reception /	Please share basic rate	This is clarified as Acrylic Emulsion Stencil Painting. Design - pattern already provided

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		Radiotherapy / LINAC / Emergency / OPD Waiting / OPD Corridor / Chemo/ MRI):Vertical Wall Painting with stencil using emulsion paint of approved shade of pattern uniformly as per manufacturers specifications, on wall surface / gypboard partitions / Gyp panneling and ceiling. cost includes surface preparation, primer coats, levelling patti Colours as per architect's detail.		as per Concept presentation. Vendor shall quote as per rates arrived accordingly.
32.	BoQ	ACRYLIC EMULSION PAINTING: (Stencil Type - 1 - Bamboo Pattern) (Reception / Radiotherapy / LINAC / Emergency / OPD Waiting / OPD Corridor / Chemo/ MRI):Vertical Wall Painting with stencil using emulsion paint of approved shade of pattern uniformly as per manufacturers specifications, on wall surface / gypboard partitions / Gyp panneling and ceiling. cost includes surface preparation, primer coats, levelling patti Colours as per architect's detail.	1) Please clarify, Items is wall graphics Film or Wall Graphic Paint.2) Also need basic Rate of Wall Graphics.	This is clarified as Acrylic Emulsion Stencil Painting. Design - pattern already provided as per Concept presentation. Vendor shall quote as per rates arrived accordingly.
33.	BoQ	Metal Ceiling (Reception)Supply and fixing of Luxalon Closed Ceiling System as manufactured by Hunter Douglas Architectural Products or Equivalent. The longitudinal panels - 150mm wide and finish as per architect's choice are clipped on to Rows of 0.6 Fe/0.95 Alu roll formed carrier swith max length of 5000mm . The panels abut each other with a narrow V-groove. Panels can be combined as	Please provide more vendors for the specified item that is based in Guwahati viz. for example, St. Gobain, USG Boral, Armstrong, Jennifer Pas, etc.	Metal Ceiling (Reception)Supply and fixing of Luxalon Closed Ceiling System as manufactured by Hunter Douglas Architectural Products or Equivalent. The longitudinal panels - 150mm wide and finish as per architect's choice are clipped on to Rows of 0.6 Fe/0.95 Alu roll formed carrier swith max length of 5000mm . The panels abut each other with a narrow V-groove. Panels can be combined as required in the

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		required in the ceiling. Panels to be manufactured from pre-painted, stove enamelled, alloy HD5050 or equal (according to EN 1396 and ECCA). All panels to be securely clipped to carriers in accordance with manufacturers recommendations, Panels to be joined in length by using the relevant Luxalon splice. Maximum panel length to be 6000 mm. System to include Wall L-panel as per architect's specification option. The price should include the cost of making any cuts and openings for lights and other fittings, all inclusive. Make : M/s Hunter Douglas. Paint Shade : 8620 Pine or similar from Armstrong / USG / Equivalent approved by Client		ceiling. Panels to be manufactured from pre-painted, stove enameled, alloy HD5050 or equal (according to EN 1396 and ECCA). All panels to be securely clipped to carriers in accordance with manufacturers recommendations, Panels to be joined in length by using the relevant Luxalon splice. Maximum panel length to be 6000 mm. System to include Wall L-panel as per architect's specification option. The price should include the cost of making any cuts and openings for lights and other fittings, all inclusive. Make : M/s Hunter Douglas. Paint Shade : 8620 Pine or similar from Armstrong / Saint Gobain ,/ USG / Equivalent approved by Client
34.	BoQ	Consultation Table:The worktop is made of 25mm thick prelaminated particle board with 2mm thick PVC Lipping on the edges. The worktop is supported on loop shape Metal Legs 50mm x50mm powder coated understructure with laminate panel. Side Storage body is a combination of 3 drawer pedestal unit and a hinged door unit and is s made of 18mm thick pre laminated partical Board conforming to IS:12823 and is hinged door unit . The back of the unit is made from 18mm prelaminated board. All the exposed edges are with 2mm PVC egde approved make banding and sealed edges are with	Cost will be without postform, specification will be as per OEM and not BOQ Can we quote for our factory make, please confirm for all furniture	No. cost shall be considered for post form. Vendor need to provide from the approved make like : Godrej / Featherlite / Durian / StyleSpa. table from the Approved make OEMs qualifying the basic requirements as per the specifications are acceptable. In case of deviation in specifications by the Approved make OEM, the Vendor shall submit specification sheet from the respective OEM and seek approval from Client / Consultant.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		0.8mm thick PVC approved make edge banding. The top side and hinged shutters are sealed with 2mm thick PVC edge banding. Back the unit are assembled by knock down fitting such as Minifix and Dowels. All the hardware and Hinges are from Hettich/Ebco.Warranty 5 years.		
35.	BoQ	Workstation L Shape:Curvilinear Workstion 1500 L x 600W x 1200 L x 600W x 1200mm Ht with pedestal unit Frame is 50 mm thick and made of Aluminium Extrusions of 1.2 mm to 1.5mm thickness. The System is complete hollow system with space for wire reticulation. All the frames will be duly power coated. All the frames are fastened together by means of M6 NUTS & BOLTS. All the frames are fitted with M10 leveling bolts, board. Race way -The race way cover are sliding type and are integrally fitting inside frame and are made out of 0.8mm-1mm thick CRCA steel & powder coated. The electrical raceway can be provided below worktop or above worktop. The partition has two integrated raceway provided one at skirting level and another at the work surface level thus ensuring separation of power and networking cables. The free space available within raceway accommodates power, data and communication cables. The cable can be taken into the frame from the floor from	Cost will be without postform, specification will be as per OEM and not BOQ	M/s Featherlite Model: Collaborate - L Shaped Laminate Finish - GREENLAM LAMINATES - 776 Java Teak Paint shade: RAL 9016 Traffic White or similar from Godrej. Interior Contractor must prepare detailed shop drawings for Furniture layout in scale detailing out the Workstation arrangement as per Vendor details. Approved makes : Godrej / Featherlite / HNI India. Workstations from the Approved make OEMs qualifying the basic requirements as per the specifications are acceptable. In case of deviation in specifications by the Approved make OEM, the Vendor shall submit specification sheet from the respective OEM and seek approval from Client / Consultant.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		the bottom. Tiles : Fabric Tile; constructed out of 5mm thick Medium Density Fiber Board(MDF) and covered with Fabric of choice. Laminate Tile; constructed out of 0.8 mm CRCA sheet and laminated Medium Density Fibre Board(MDF) Bottom Row of steel Tile; Made out of 5mm-8mm thick thick pre-laminated Medium Density Fiber Board (MDF) Bottom Row of steel M/s Featherlite Model: Collaborate - L Shaped Laminate Finish - GREENLAM LAMINATES - 776 Java Teak Paint shade: RAL 9016 Traffic White or matching equivalent from Godrej / Featherlite / Durian / StyleSpa / Herman Miller / Wipro / Steelcase. Interior Contractor must prepare detailed shop drawings for Furniture layout in scale detailing out the Workstation arrangement as per Vendor details.		
36.	BoQ	Workstation 2:Curvilinear Workstation 2000 L x 750 W x 1200mm Height with pedestal unit Frame is 50 mm thick and made of Aluminium Extrusions of 1.2 mm to 1.5mm thickness. The System is complete hollow system with space for wire reticulation. All the frames will be duly power coated. All the frames are fastened together by means of M6 NUTS & BOLTS. All the frames are fitted with M10 levelling bolts, board. Race way -The	Cost will be without postform, specification will be as per OEM and not BOQ	M/s Featherlite Collaborate Model: Collaborate Laminate Finish - GREENLAM LAMINATES - 776 Java Teak Paint shade: RAL 9016 Traffic White or similar from Godrej. Interior Contractor must prepare detailed shop drawings for Furniture layout in scale detailing out the Workstation arrangement as per Vendor details. Approved makes : Godrej / Featherlite /HNI India.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		race way cover is sliding type and are integrally fitting inside frame and are made from 0.8mm-1mm thick CRCA steel & powder coated. The electrical raceway can be provided below worktop or above worktop. The partition has two integrated raceways provided one at skirting level and another at the work surface level thus ensuring separation of power and networking cables. The free space available within raceway accommodates power, data and communication cables. The cable can be taken into the frame from the floor from the bottom. Tiles: Fabric Tile; constructed out of 5mm thick Medium Density Fiber Board (MDF) and covered with Fabric of choice. Laminate Tile: constructed out of 0.8 mm CRCA sheet and laminated Medium Density Fibre Board (MDF) Bottom Row of steel Tile; Made from 5mm-8mm thick pre-laminated Medium Density Fiber Board (MDF) Bottom Row of steel Tile; Constructed finished in epoxy powder coating. Can be given with plain /perforations/embossed finishes Magnetic tile; Constructed out of 0.8mm Galvanized sheet and covered with fabric of choice. Whiteboard marker tile: Made from 4mm MDF with 1mm glossy highly wear resistant face laminate-Total thickness is 5mm. Tabletops are of 25mm		Workstations from the Approved make OEMs qualifying the basic requirements as per the specifications are acceptable. In case of deviation in specifications by the Approved make OEM, the Vendor shall submit specification sheet from the respective OEM and seek approval from Client / Consultant.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		thick pre-laminated particle boards conforming to IS:12823 Interior Grade. All Worktops to have Metal Insets for fixing screws. Specially designed powder coated M.S brackets having 2mm thickness fixed to the partition frame support the tabletops. Sealed edge in tabletops are with 2mm thick PVC edge banding on working side and 0.8mm thick edge banding on non-working side. Legs are made of powder coated steel 50mmx50mm section. Cross Member are in CRCA steel and the Beam is made of MS of 1.5mm thickness in powder coated finish of 50 microns thickness -Each workstation has 3D raver pedestal unit of size 400mm L x 450mm D x 680 mm made up of 18mm thick pre-lam particle board conforming to IS:12823 Interior Grade with 3 Drawer (2 Drawer + 1 Filing) with roller side mechanism for 2 Drawers and Ball bearing slide for 1 Filing unit. Warranty 10 years. Make: Featherlite, Model: Collaborate. Laminate Finish - GREENLAM LAMINATES - 776 Java Teak; Paint shade: RAL 9016 Traffic White		
37.	BoQ	Conference table:10 seater Provinding and placing Meeting Room table 10 Seater in "U" Shape in "Trent" Table Tops- Available in standard modules 1500mm Lx 750mm D, made of 25mm	Cost will be without postform, specification will be as per OEM and not BOQ	Standard sizes to be followed as per Seating required. Interior Contractor to prepare detailed Furniture layout drawings as per Interior planning. Approved makes : Godrej / Featherlite / Durian / StyleSpa.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		thick postformed partlice Board with waterfall top edges finished in postlaminated finish for better aesthetics and long lasting use. Understructure - Legs made of 18mm thick standard Black colour prelaminated particle Board panels interconnected with 18mm thick standard Black matt colour pre- Laminated modesty panels with height adjustable levels to take care of uneven floors. Wire management-concealed wire management to take care of basic wiring requirements both horizontally and vertically. Cable Tray is mounted on the inner side of modesty panel for horizontal wire carrying. Vertical wire management is through flexible vertical wire manager. Slots for Mounting data and Electric Switches and Sockets are provided on cover section of Cable Tray. Standard table top height- 750mm. Designed for Flexibility through modular Construction , Postformed curvica Finish Tops for Elegent and classic Looks. Provision for easy wire management, radeable/reconfigurable for future needs. Corners are provided in Black paint MDF Surface in 25mm thicknees. Corners are supported on 63.5mm painted Metal pole with Leveller for Height Adjustment. Warranty 5 years.		Conference table from the Approved make OEMs qualifying the basic requirements as per the specifications are acceptable. In case of deviation in specifications by the Approved make OEM, the Vendor shall submit specification sheet from the respective OEM and seek approval from Client / Consultant.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
38.	BoQ	Conference table:Standard 8 seater sizes to be followed. Interior Contractor to prepare detailed Furniture layout drawings as per Interior planning. Approved makes : Godrej / Featherlite / Durian / StyleSpa / Herman Miller	Cost will be without postform, specification will be as per OEM and not BOQ	Standard sizes to be followed as per Seating required. Interior Contractor to prepare detailed Furniture layout drawings as per Interior planning. Approved makes : Godrej / Featherlite / Durian / StyleSpa. Conference table from the Approved make OEMs qualifying the basic requirements as per the specifications are acceptable. In case of deviation in specifications by the Approved make OEM, the Vendor shall submit specification sheet from the respective OEM and seek approval from Client / Consultant.
39.	BoQ	Supplying at site the CAFETERIA tables or equivalent of size mentioned below. The table top is made up with Iso top. Tables corner should be have rounded corners on all the four sides for safety. Under structure will be of SS base and foldable etc., all complete.	Can we quote for our factory make	Providing and supplying 20-25mm thick ISOTOP tables with table top fixed onto SS (brush finished) square tubes min. 50 x 50mm understructure with necessary bush and accessories etc. All complete. Make Featherlite Model - Café chrome ISOTOP or Similar equivalent from Godrej / Featherlite / Durian / StyleSpa
40.	BoQ	Full Height Storage Unit (LINAC):Providing & fixing full height storages with 19mm ply length as per drawing, depth of 450mm, 2700mm height, all as per architectural detail drawings, with carcass to be of 22mm thk comercial ply and shutters of 25thk commercial ply finished with Laminate inside & outside with factory fit edge banding. Storage to have necessary shelves formed of 19mm ply finished with 0.8mm laminate. Shutters to be	Please share length	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		postformed. Shutters to be provided with necessary hardwares like spring loaded hinges, tower bolts, SS handles, magnetic catchers and locks etc., of approved make and quality. Rate to be inclusive of all necessary hardware -box hinge - (0mm cranking Model:316.31.500),9.5mm cranking (Model:316.31.501), locksets, spring loaded shutter latch inside, all cabinet hardware to be of make: Hettich.		
41.	BoQ	Doctor's Consultation Worktable:Size- Main Table : 1500 x 750, Return Table :900 x 450,Table Top -Prelam PVC lipping ,Understructure : Aluminium,RaceWay - below Table,Accessories : Mobile Pedestal - 1 No (2 draws ans 1 openable shutter) & Side Storages with shelves with 2 openable shutters, all complete.	Can we quote for our factory make	No. Shall be supplied as per approved makes only. Client approval shall be taken before the supply. So that across the sites uniformity can be maintained.
42.	BoQ	Service Counter (LINAC):Providing & fixing of 19mm thk granite counter of 600mm depth formed out of 19mm thk BWP ply and cladded with granite with edges as per details. To have storage below counter as per details and to be made of 19mm BWP ply with lipped edges finished with 1mm thk laminate outside and inside to be finished with 0.8mm laminate. Shutters to be post formed laminate.Shutters to be fixed with all necessary accessories like hinges, tower bolts, magnetic catchers, locks, SS handles	Please share basic rate of granite	Base Rate: 250 Rs per sq. ft cut to size landed cost.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		etc., as directed by architect. Provide adjustable shelves finished with 0.8mm laminate as per details. Also to provide necessary cut outs for fixing of switches, sockets, wash basin all complete. The cost to include silicon sealant at the edges as per details. Rate to include 150mm granite band above the counter as per details. Cost should include Borer / Antitermite treatment for salwood and plywood. Table Size: 8000mm x 1050mm height x 675mm(depth)		
43.	BoQ	Under Counter Storage Units (All areas):Providing best quality below counter storage 850mm high with Aluminium frame with extruded built up sections of wall thickness not less than 2.0mm conforming to IS:733 7 IS:1285 of approved make, joints mitered and joined with Hettich Intermat 9936 fast assembly self closing nickel palated steel hinge inside to the concrete block of 150x100x100mm with the help of 75mm expandable dash fastner. Shutter, backing & Intermediate shelves shall be with Factory made 20mm MR Ply with 1mm Laminate finish on the outside and 0.8mm laminate finish on the inside of Approved make, the cost inclusive of all with necessary accessories like locks, SS brush finished handle, Magnetic catch, Hinges, Screw, hardware etc. grommet holes, all complete, as per	UOM mentioned for under counter Storage is in Nos, Need to be in RMT, Please clarify.	Please refer Revised BoQ

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		architectural detail drawing. Laminate colours as per architect's approval with conveyance and taxes of all materials complete in all respect. The Under counter storage shall be of 850mm ht and 600mm depth as per any standard counter depth. This shall be measured in RM units for the total length of this counter where the under counter storage is provided.		
44.	BoQ	Under Counter Storage Units (All areas):Providing best quality below counter storage 850mm high with Aluminium frame with extruded built up sections of wall thickness not less than 2.0mm conforming to IS:733 7 IS:1285 of approved make, joints mitered and joined with Hettich Intermat 9936 fast assembly self closing nickel plated steel hinge inside to the concrete block of 150x100x100mm with the help of 75mm expandable dash fastener. Shutter, backing & Intermediate shelves shall be with Factory made 20mm MR Ply with 1mm Laminate finish on the outside and 0.8mm laminate finish on the inside of Approved make, the cost inclusive of all with necessary accessories like locks, SS brush finished handle, Magnetic catch, Hinges, Screw, hardware etc. grommet holes, all complete, as per architectural detail drawing. Laminate	Please confirm unit of measurement, it should be RMT	UoM is RMT

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		colours as per architect's approval with conveyance and taxes of all materials complete in all respect. The Under counter storage shall be of 850mm ht and 600mm depth as per any standard counter depth. This shall be measured in RM units for the total length of this counter where the under counter storage is provided.		
45.	BoQ	Lockers:Providing and supplying steel single Tower Locker Cabinets of approved make & model with in-built Locks having dimension of 1800mm H x460mm D x390mm W made of 0.8mm thick CRCA sheet duly powder coated to thickness of 40-60 micron. Each vertical unit has SIX Nos Locker unit. Each unit has independent door with concealed hinges and 7 lever cam lock and label holder the product has leveler for good ground support. All the components are finished 40 to 50 microns thick epoxy polyester powder coating oven baked at 180to 200 deg.C. The above furniture should be as per specification and sample approved by client. Make: Featherlite Model : C/G - LSS60-1 , Locker Single column - 6 door starter + add on units with lock&key / Padlock provision or equivalent from Godrej / Durian / StyleSpa / Herman Miller / Wipro	Lead time will be 10 - 12 weeks	Vendor need to follow the overall project timelines. Vendor should explore the alternate makes mentioned in BoQ.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		/Steelcase.Note: Detail layout drawing to be prepared by Interior Contractor as part of Furniture layouts.		
46.	BoQ	Colour Frost film:A) Supply & Application of Frost/Privacy Film for Glass Partitions .(The successful vendor should submit 10 years Warranty certificate to the clients. Product to be certified by Manufacturer's Representative) (Reception)B) Supply & Application of Frost/Privacy Film for Glass Partitions .(The successful vendor should submit 10 years Warranty certificate to the clients. Product to be certified by Manufacturer's Representative) (ICU)Make: 3M or equivalent make. NOTE : Interior Contractor must develop the Custom Design with 3M or equivalent make using the Graphics Vendor. The Film pattern should be matching in line with the Concept Presentation.	Please share basic rate	Make: 3M or equivalent make. Vendor Contact details as Below: M/s SIGNTIST Graphics - Mr. Praveen, 9884948600 or any others as per Concept Presentation & Specifications NOTE : Interior Contractor must develop the Custom Design with 3M or equivalent make using the Graphics Vendor. The Film pattern should be matching in line with the Concept Presentation.
47.	BoQ	Wall Vinyl graphics (Single Room / Consultation Room / Cafeteria):Providing and fixing commercial grade Wall vinyl graphics of approved design / pattern of approved make on to already prepared base with recommended adhesive of approved make which have 100% washable, scratch resistance, peel proof, and fire retardant properties. NOTE : Interior Contractor must develop all the necessary Vinyl Graphics in required resolution using the Graphics	Please share basic rate	Vendor Contact details as Below: M/s Emagine India- 9916631250 or M/s Blue Pebble- 9768199800 or M/s SIGNTIST Graphics - Mr. Praveen, 9884948600 NOTE : Interior Contractor must develop all the necessary Vinyl Graphics in required resolution using the Graphics Vendor. The Graphics should be matching in line with the Concept Presentation using Presets from the Vendor / Custom developed subject to Approval by Client / Architect.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		Vendor. The Graphics should be matching in line with the Concept Presentation using Presets from the Vendor / Custom developed subject to Approval by Client / Architect.		
48.	BoQ	Roller Blinds:>Providing & fixing Roller blinds confirming to specifications, including spring mechanism >The Drive units -Shall be of moulded plastic with rectangular support pin and inserted into the tube end .It shall be driven by a ball chain pulley with ball chain and can be positioned at right hand or left hand side of the shade.The shade when lowering or raising ,shall be automatically locked in position upon release of the ball chain by means of built in friction lock. >End Plug-Shall be moulded of plastic with alocation pin .The plug shall be inserted into tube end.(Opposite to drive unit) >Support Brackets-Shall be of zinc plated steel & provided with moulded plastic covers and used in right hand or left hand positions differentiated by the acceptance of the rectangular drive unit support or the round idler plug pin. >Bottom Rails-Shall be stiffening element inserted into abottom rod pocket.The material may be timber ,PVC covered steel tube or VB bottom rail. >Ball Chain -Shall be 2mm diameter cord with 4.5mm diameter acetal balls	Please share basic rate	Phifer- P75 PEARL / V16 GREY / Equivalent approved shade Vendor details as follows: M/s Phifer - Mr.Yogesh, 8884311112 M/s Vista - Mr.V.FAIAZ AHAMED, 9840466044 M/s Hunter Douglas - Mr.Subramani, 8754448500

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		moulded co-axially to it on 6mm pitch to form a endless ball chain .It is used for raising or lowering action of the shades. >Fabric 1) Basic material -100% antimicrobial - polyster - trnsculent 2) fabric weight -170g/sqm 3) Thickness -4mm 5) Finishing -Double side vinyl acetate, pigment coated >Light Fitness -Confirming to DIN54004/DIN EN ISO 105-B02>/5-6 >Shrinkage % ge-Confirming DIN 53892 B2 <0.5% > 1% Perforation factor - (Code- Solaric Fabric Panel-1%-Sol Series-001)		
49.	BoQ	PHARMACY RACK:Interior Contractor shall prepare detailed layout of the Pharmacy with Furniture layout & details from Vendor for Client approval. Over the Counter Drug Store racks to be provided with combination of open shelves and closed storage racks type. Type -2 shall be showcase racks with sliding glass shutters in tracks of approved quality and necessary locking arrangements. Type1-70 % & Type -2 -30% to be considered and shall be actual as per final layout approved by the Client.	Please share size and vendor contact	for basic size please refer drawings. Height of the rack shall be considered as 8 ft. Detailed drawing shall be prepared by Vendor for approval.
50.	BoQ	Floor / Wall Rail System (Circular Columns in Reception / OPD Waiting Feature Wall / IPD Waiting Feature Wall):Supply and	Please share drawing to quote, without drawing wont be able to quote	Height shall be min. 300mm height. Details for each specific areas of application shall be prepared by bidder in reference to the

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		installation of 50mm Dia Wall or Floor mounted Rail system (as per site condition) on columns of 304 grade steel as directed of approved make - Gradus or Equallent.		Concept presentation views. GRADUS - SS Floor railing system - Heavy Duty pillars or equivalent
51.	BoQ	CHANGE ROOM BENCH:MS powder coated change room bench of size (1500mm (L) x 450mm (W) x 450mm (H). Featherlite - Model : Collab PU Bench or similar from Godrej / Featherlite / Durian / Style spa / Equivalent. Refer Loose furniture Vendor / supplier details	Product not available with featherlite, can we quote local make. Please confirm	Refer Revised BoQ
52.	BoQ	Display Boards / LED TV Supports: (Reception / Waiting Areas / Wards / Single Rooms)Providing & fixing MS SUPPORTS in 50mm X 50mm MS angle with base plate & anchor bolts for digital internal display board finished with approved paint to for specific Model of LED (LED sizes 32 inch to 65 inches) as per architect's specification, all complete..	Please confirm what size to consider 32 or 65, as rate will vary	Its QRO item.
53.	BoQ	SS Signage: B) SS Signage (Emergency) Size : Height of each Lettering shall be 300mm	Please share length	for basic size please refer drawings. Detailed drawing shall be prepared by Vendor for approval.
54.	BoQ	A) Reception SS Logo + Lettering fixed on wall / paneling As per Concept Presentation & Specifications. Interior Contractor shall prepare detail shop drawings for all the Signages. Overall logo Size is ACCF logo - 2155mm x 1165mm	Need Vendor Details of Signages Work.	Vendor Contact details as Below: M/s SIGHTIST Graphics - Mr. Praveen, 9884948600 or any others as per Concept Presentation & Specifications. Interior Contractor shall prepare detail shop drawings for all the Signages.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
55.	BoQ	B) SS Signage (Emergency) Size : Height of each Lettering shall be 300mm	Need Vendor Details of Signages Work.	Vendor Contact details as Below: M/s SIGHTIST Graphics - Mr. Praveen, 9884948600 or any others as per Concept Presentation & Specifications. Interior Contractor shall prepare detail shop drawings for all the Signages.
56.	BoQ	C) Lift Lobby Floor Indication SS Signage As per Concept Presentation & Specifications. Interior Contractor shall prepare detail shop drawings for all the Signages. Size: Floor indication - 950mm x 1100mm	Need Vendor Details of Signages Work.	Vendor Contact details as Below: M/s SIGHTIST Graphics - Mr. Praveen, 9884948600 or any others as per Concept Presentation & Specifications. Interior Contractor shall prepare detail shop drawings for all the Signages.
57.	BoQ	Artwork	Need Basic Rate of Art Work.	Alternate Vendor details: M/s MOJARTO ART. https://www.mojarto.com Regd. Office: B 50 A, 2nd Floor Archana Complex, Greater Kailash – I, New Delhi 110048 Corporate Office: Archana Complex, Greater Kailash Part 1, New Delhi -110048, India
58.	BoQ	Artwork - 1 - 900x1500mm	M/s Yasinth enterprises, does not deal with those product, Please share basic rate	Alternate Vendor details: M/s MOJARTO ART. https://www.mojarto.com Regd. Office: B 50 A, 2nd Floor Archana Complex, Greater Kailash – I, New Delhi 110048 Corporate Office: Archana Complex, Greater Kailash Part 1, New Delhi -110048, India

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
59.	BoQ	Artwork - 2 - SS PLATE INCL detached SS Lettering - 750x1200mm as per detail drawing using SS plate	M/s Yasinth enterprises, does not deal with those product, Please share basic rate	Alternate Vendor details: M/s MOJARTO ART. https://www.mojarto.com Regd. Office: B 50 A, 2nd Floor Archana Complex, Greater Kailash – I, New Delhi 110048 Corporate Office: Archana Complex, Greater Kailash Part 1, New Delhi -110048, India
60.	BoQ	Artwork - 4 (Artist's Painting- Printed on Canvas) (Waiting/ Emergency Room / LINAC / Consultation Room /) - 600X600MM	M/s Yasinth enterprises, does not deal with those product, Please share basic rate	Alternate Vendor details: M/s MOJARTO ART. https://www.mojarto.com Regd. Office: B 50 A, 2nd Floor Archana Complex, Greater Kailash – I, New Delhi 110048 Corporate Office: Archana Complex, Greater Kailash Part 1, New Delhi -110048, India
61.	BoQ	Stainless Steel Tandem Chairs (Reception / Radiotherapy / OPD Waiting / Emergency)A) 4S	Please share size	4S Steel Chair with PU Seat in shade as approved by Architect. Approved Make: Featherlite Model: Sleek Cushion Tandem or equivalent from Godrej / Durian / StyleSpa / Herman Miller / Wipro / Steelcase
62.	BoQ	Stainless Steel Tandem Chairs (Reception / Radiotherapy / OPD Waiting / Emergency) -Steel Chair with PU Seat in shade as approved by Architect. Make - Featherlite Model: Sleek Cushion Tandem SJ-820A-2 & 3 Seater. Note : Total Seating capacity to be	Tandem Chair in Stainless Steel is not readily available with Godrej, Featherlite, Durian, Stylespa, Wipro, Herman Miller and Steelcase. However, they can provide the same on order for a minimum quantity for 100 pcs each with a lead time of 60 to 90 days, however, the same is readily available in	Available with Featherlite.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
		matched as per Furniture layout by Interior Contractor. Necessary Furniture layouts to be prepared by Interior Contractor matching equivalent from Godrej / Durian / StyleSpa / Herman Miller / Wipro / Steelcase	chrome finish, but 2S, 4S and 5S need additional lead time for delivery. In this context, we would like to mention that Amber furniture (previously specified by you) as well as Rastogi furniture (Jaipur based) having client network throughout Pan India can provide the same within 15 days. Please do the needful by adding these vendors as we have to complete the work with a very short span of time.	
63.	BoQ	Stainless Steel Tandem Chairs (Reception / Radiotherapy / OPD Waiting / Emergency) -Steel Chair with PU Seat in shade as approved by Architect. Make - Featherlite Model: Sleek Cushion Tandem SJ-820A-2 & 3 Seater. Note : Total Seating capacity to be matched as per Furniture layout by Interior Contractor. Necessary Furniture layouts to be prepared by Interior Contractor matching equivalent from Godrej / Durian / StyleSpa / Herman Miller / Wipro / Steelcase	Please share vendor contact	Makes are given. Vendors need to arrange the supplies.
64.	General query	General query	Is there requirement for Site office for PMC/Client/Architect that needs to be factored in our quote, please confirm. If yes please specify requirements	Yes. However, space shall be provided by ACCF. Bidder is also required to keep security of its material. Storage space shall be provided by ACCF.
65.	General query	General query	Basic rates - Are these landed at site, GST extra. Please define	Basic price shall include all other taxes and charges(i.e. import duty, transport charge, Excise etc.), except GST.

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
66.	General query	General query	As the previous tender stood cancel, but the EMD (BG) is valid till 2022 and the tender id was not mentioned in the BG as per given format, we shall submit the same BG for this tender.Please confirm	Yes. It will be considered. Bidder has to submit the letter on the letterhead with BG stating this tender no. BG should have validity as per this tender dates.
67.	General query	General query	Kindly confirm, it is only hard copy submission, except the EMD, Declaration & Power of Attorney in hard copy	Hard/Original copy of EMD, Power of attorney, Declaration need to be submitted. Scan copy of these documents shall also uploaded.
68.	General query site	Stone Veneer Sheet	M/s Elite Corporation LLP-Does not deal in particular item.	Stonetech, Second vendor contact No: jolly Banerjee, 9884034324 Alternate for Same material type Mr. Shamugam Sundar Contact No: 9894118343 Make: StoneLam, Alpha Series: ossidiana Vena Scura / Gamma Series Oxide Nero / Beta series, Pietra Di Savoia Antracite
69.	General query site	Artificial Moss	M/s Kusal Flora-Does not deal in particular item.	M/s. Kusal gardens Contact: 9677232413
70.	General query site	Metal Ceiling	M/s Hunter Douglas-No contact details provided by you.	M/s Hunter Douglas is a major brand in India. Hunter Douglas India 4055, Central Express Way, Sector 23 SRICITY, Varadaiah Palem Mandal Near Tada Check Post, Chennai Nellore High Way, Andhra Pradesh - 601201 Tel: Toll-free: 1800 121 1919 / 91-44 71379300 Email: contact@hunterdouglas.in Bidder

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
				shall locate necessary dealer / supplier for the same.
71.	General query site	Artefacts/ Arts Painting	M/s Yasinth Enterprise-No response	Alternate Vendor details: M/s MOJARTO ART. https://www.mojarto.com Regd. Office: B 50 A, 2nd Floor Archana Complex, Greater Kailash – I, New Delhi 110048 Corporate Office: Archana Complex, Greater Kailash Part 1, New Delhi -110048, India
72.	General query site	Loose Furniture	M/s Amardeep-No response	For all Loose Furnitures – Few Vendor/ Supplier details as provided below. Alternately, the vendor can contact the Approved makes OEM directly / locate local dealers through the OEM company itself : M/s Seating World -Mr.Dayanidhi, 8754493843 www. seatingworldindia.com or M/s ALBANS - Mr. Farath, 7889759907 or M/s Amardeep - Mr. Raju, 9731955252 or M/s Furniture Hub - Mr Nagesh, 9741688188 or M/s Amber - Mr Balaji, 009444379963
73.	General query site	Loose Furniture	M/s Amber-No response	For all Loose Furnitures – Few Vendor/ Supplier details as provided below. Alternately, the vendor can contact the Approved makes OEM directly / locate local dealers through the OEM company itself : M/s Seating World -Mr.Dayanidhi, 8754493843 www. seatingworldindia.com or

S No	Tender Clause no.	Tender Clause	Comments and Query raised	Remarks for Resolution
				M/s ALBANS - Mr. Farath, 7889759907 or M/s Amardeep - Mr. Raju, 9731955252 or M/s Furniture Hub - Mr Nagesh, 9741688188 or M/s Amber - Mr Balaji, 009444379963
74.	General query site	Modular Aluminium Skirting	Mr. Hitesh-No proper response.	Alternate contact : M/s Bottomline Mr. Santhosh, Contact: 9886764042

Sd

Head Procurement